

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Kingman County, Sec. 15 Twp. 28S Rge. (E) 5 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE NW SW

Lease Owner Beardmore Drilling Company

Lease Name Foley Well No. 5

Office Address 603 Petroleum Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 22 19 52

Application for plugging filed May 22 19 52

Application for plugging approved May 22 19 52

Plugging commenced May 22 19 52

Plugging completed May 22 19 52

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, Box 597, McPherson, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3865 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	125	8-5/8	125'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

Mud to 160', set plug and dump 25 sacks cement;
Mud to 35', set plug and dump 5 sack cement to complete.

RECEIVED
STATE CORPORATION COMMISSION

JUN 2 - 1952 06.02.52

Name of Plugging Contractor Beardmore Drilling Company

Address 603 Petroleum Bldg., Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, Heber Beardmore, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore

603 Petroleum Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of May, 19 52.

Edward P. Tolle
Notary Public.

My commission expires January 28, 1956

PLUGGING
FILE SEC-107-2816
BOOK PAGE 19 LINE 2

15-095-0735-0500

Foley No. 5

NE NW SW
Section 15-28S-5W
Kingman County, Kansas

Drilled by: Beardmore Drilling Company
Drilled for: Beardmore, et al

Casing Record:

8-5/8" 125' w/100 Sacks Cement

Dated Commenced: May 13, 1952
Date completed: May 22, 1952

Elevation: DF 1397
GR 1395

<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5
Sand Soil - Clay	25
Red Rock - Shale	123
Shale - Shells	730
Shale - Lime	845
Lime Broken	1315
Shale - Shells	1910
Shale - Lime	2510
Lime - Shale	2815
Shale - Lime	2950
Lime - Shale	3105
Lime Broken	3185
Lime	3790
Lime Chat	3822
Chat Lime	3835
Lime	3865 TD

D & A

TOPS:

Mississippi 3800

DST #1 - 3811-3822 - Open 1 hour, good blow, gas in 50 minutes, estimated 50,000
Shut in 15 minutes and recovered 90' gas cut mud, BHP 435#

DST #2 - 3823-3843 - Open 1 hour, good blow, shut in 15 minutes, BHP 510#, Recovered
250 feet mud slightly gas cut, few specks oil.

RECEIVED
CONSERVATION COMMISSIONER

STATE OF KANSAS

JUN 2 - 1952

COUNTY OF SEDGWICK

SS

CONSERVATION DIVISION
Wichita, Kansas

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the above-described, to the best of my knowledge and belief.

W. H. Beardmore

Subscribed and sworn to before me this 28th day of May, 1952.

My Commission Expires: January 28, 1956

Leonard P. Tolle
Notary Public

PLUGGING
FILE SEC 15T-28S-5W
BOOK PAGE 19 LINE 3