

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH


Locate well correctly on above  
Section Plat

Kingman County. Sec. 16 Twp. 28S Rge. 5 (E) (W)  
Location as "NE/CNW/SW" or footage from lines 990'S 330'W of N/4 Corner  
Lease Owner Cities Service Oil Company  
Lease Name Palmer "B" Well No. 3  
Office Address Box 31, Augusta, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 4-10 19 63  
Application for plugging filed \_\_\_\_\_ 19 \_\_\_\_\_  
Application for plugging approved 4-10 19 63  
Plugging commenced 4-10 19 63  
Plugging completed 4-10 19 63  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3870' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped in 25 sacks cement at 3800', pulled drill pipe, fill hole with mud to 215', ran plug - 1/4 sack hulls, 25 sacks cement, fill hole to 40', ran plug - 1/4 sack hulls, cemented with 10 sacks, ran 3 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

APR 17 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company  
Address 814 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.  
J. R. Hutchinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. R. Hutchinson  
Box 31, Augusta, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15<sup>th</sup> day of April, 19 63

Glenn B. Carmack

My commission expires March 12, 1966

Notary Public.



15-095-013170000

ROTARY DRILLING LOG

OWNER: Cities Service Oil Company      CASING: Set 8 5/8" surface casing  
 CONTRACTOR: Prime Drilling Company      @ 219', 160 ex HAS Posmiz  
 LEASE: Palmer "B" #3  
 LOCATION: SE NE NW Sec. 14-28-5W  
 Kingman County, Kansas

0 - 30	Sand
30 - 165	Red Rock
165 - 215	Red Rock & Shale
215 - 319	Red Bed
319 - 475	Shale & Shells
475 - 575	Salt & Shale
575 - 720	Shale & Shells
720 - 762	Lime & Shale
762 - 1223	Lime
1223 - 1400	Lime & Shale Streaks
1400 - 1845	Lime & Shale
1845 - 1865	Shale & Lime Streaks
1865 - 1920	Sand
1920 - 2010	Shale & Lime Streaks
2010 - 2080	Lime & Shale Streaks
2080 - 2150	Lime
2150 - 2277	Shale & Lime
2277 - 2785	Lime & Shale
2785 - 2965	Shale & Lime
2965 - 3430	Lime
3430 - 3520	Lime & Shale Streaks
3520 - 3530	Lime & Shale
3530 - 3585	Cherty Lime
3585 - 3648	Lime & Shale
3648 - 3798	Shale & Lime Streaks
3798 - 3813	Chat
3813 - 3828	Chert
3828 - 3846	Miss Chat
3846 - 3868	Miss Lime
3868	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION

APR 18 1963

CONSERVATION DIVISION  
Wichita, Kansas

D & A

We certify that the above log is true and correct to the best of our knowledge and belief.

PRIME DRILLING COMPANY

BY R. R. Mc Nicol  
R. R. Mc Nicol