


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Kingman County. Sec. 16 Twp. 28S Rge. 5 (W)  
Location as "NE/CNW<sup>1</sup>/<sub>4</sub>SW<sup>1</sup>/<sub>4</sub>" or footage from lines SW SW NE  
Lease Owner Smitherman & Cohen, Et al  
Lease Name Bolinger Well No. 2  
Office Address  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 5 19 51  
Application for plugging filed October 3 19 51  
Application for plugging approved October 4 19 51  
Plugging commenced October 4 19 51  
Plugging completed October 4 19 51  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Depth to top Bottom Total Depth of Well 3812 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2"	3811' 6"	2900'
				8"	156'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bridge plug & dumped 6 sacks of cement @ 3805 filled w/ mud to 1651 filled w/ rock & sand to 1551 dumper 15 sacks of cement filled w/ mud capped w/5 sacks of cement and filled to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC - 1 1951  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Hall & Prather Drilling Co.  
Address Route #1 Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, SS.  
L. C. Smitherman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. C. Smitherman*  
P. O. Box 692 El Dorado, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of *Oct*, 19 51  
*Edith A. Higgett*  
Notary Public.

PLUGGING  
FILE SEC 16 T 28 R 5  
BOOK PAGE 113 LINE 41

15095-01486-0000

BOLINGER WELL #2

Company - Smitherman & Cohen, Et al  
 Contractors - Smitherman & Cohen Drilling Co.  
 Commenced - 6-19-51  
 Completed - 7-5-51  
 Total Depth - 3812'  
 I. P. - 25 Ebl.

Loc. SW SW NE, Sec. 16-28S-5W  
 Kingman County, Kansas.  
 Elev. 1399 RB  
 Casing:  
 8" 156' cemented w/100 sacks  
 5 1/2" 3811 1/2' cemented w/ 50 sacks

Figures Indicate Bottom of Formations

<u>FORMATION</u>	<u>DEPTH</u>
Sand & Shale	158
Cement	164
Shale & Shells	765
Shale & Lime	815
Shale, Sand & Salt	884
Shale & Lime	965
Lime & Shale	1135
Lime	1385
Lime & Shale	1510
Shale & Lime	2390
Lime & Shale	2800
Shale & Lime	2985
Lime	3425
Lime & Shale	3480
Shale & Lime	3550
Lime & Shale	3797
Lime, Cherty	3812 T.D.

RECEIVED  
 STATE COMMISSION  
 DEC - 1 1951  
 CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC. 16 T. 28 R. 5W  
 BOOK PAGE 113 LINE 41