


15095-20594000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County, Sec. 10 Twp. 28S Rge. 7W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C of SE SW
Lease Owner Mack Oil Company
Lease Name Sparks #1 Well No.
Office Address RR #3, Box 162, Great Bend, Ks 67530
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Flugging commenced 10/3/80 19
Plugging completed 10/3/80 19
Reason for abandonment of well or producing formation
Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owen
Producing formation Depth to top Bottom Total Depth of Well 4400'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	226'	None
				4-1/2"	4069'	3412'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Squeezed hole with 15 sacks gel, 8 sacks hulls and 10 sacks gel. Released plug and displaced with 150 sacks common cement, 2% gel and 3% cc.

Plugging complete.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of October, 1980



My commission expires

Joan Kelso
Notary Public.

DRILLER'S LOG

15-095-20594-0000

COMPANY: Mack Oil Company

SEC. 10 T. 28S R. 7W

WELL NAME: Sparks #1

LOC. C SE SW

COUNTY: Kingman

RIG NO. #7

TOTAL DEPTH 4400'

ELEVATION 1548'

COMMENCED: 6-12-77

COMPLETED: 6-24-77

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 226' w/200 sx. common, 2% gel, 3% cc.

PRODUCTION: 4 1/2" @ 4064' w/25 sx. 50/50 poz., 125 sx. common, 3/4% CFR2
18% salt.

LOG

(Figures Indicate Bottom of Formations)

Shale	1355
Shale & Lime	1653
Lime & Shale	2012
Shale & Lime	2785
Lime & Shale	2963
Shale & Lime	3300
Lime	4400
<u>ROTARY TOTAL DEPTH</u>	<u>4400</u>

RECEIVED
STATE CORPORATION COMMISSION
JUL - 7 1980
CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.
upon oath state that the above and foregoing is a true and correct copy of the log of the
Sparks #1 well.

Wilson Rains

Wilson Rains

Subscribed and sworn to before me this 27 day of June, 1977.

My Appointment Expires:

10-4-79

Juanita M. Green
Juanita M. Green

