


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kingman County, Sec. 11 Twp. 28 Rge. (E) 7(W)  
Location as "NE/CNWxSWx" or footage from lines. C SW SE  
Lease Owner Pickrell Drilling Company  
Lease Name Sparks "F" Well No. 1  
Office Address 705 4th National Bank Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 6, 1964  
Application for plugging filed July 6, 1964  
Application for plugging approved July 6, 1964  
Plugging commenced July 6, 1964  
Plugging completed July 6, 1964  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4300 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	218'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 205'. Set plug. Cemented with  
25 sacks cement. Heavy mud to 40'. Set plug.  
Cemented with 10 sacks cement to bottom of  
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 13 1964  
7-13-64  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 4th National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Gerald W. Pike (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.

(Signature) Gerald W. Pike  
705 4th National Bank Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of July, 1964

My commission expires JUNE 21, 1966 Maxine Blackman Notary Public.

**ROTARY DRILLING LOG** 15-095-004770000

COMPANY: Pickrell Drilling Company Rotary Drilling Commenced 6-23-64  
 705 4th National Bank Building  
 Wichita, Kansas Rotary Drilling Completed 7--6-64  
 LOCATION: Sparks "F" No. 1, C SW SE Section 11-28-7W, Kingman County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
**Wichita, Kansas**

CASING RECORD: (10 jts) 8 5/8" surface casing set at 218' with 155 sacks cement.  
 Circulated. Completed 6:15 P.M. June 23, 1964. No oil string  
 run. D & A.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

95	Top Soil & Rock	<u>C. F. S.</u>
219	Red Rock	2882
1000	Red Rock & Shale	2940
2911	Lime & Shale	3460
2941	Lime	3523
3040	Shale & Sand	3550
3210	Sand, Shale & Lime	3596
3290	Lime	3905
3355	K. C. Lime	3910
3475	Lime	4277
3523	K. C. Lime	4280
3675	Lime	4300
3715	Lime & Shale	
3771	Lime	<u>Slope Tests</u>
3895	Shale & Lime	2500
3910	Chat - Mississippian	3000
4174	Mississippian	3500
4218	Mississippian & Kinderhook	4000
4280	Viola	
4297	Viola & Simpson	<u>S. L. M.</u>
4300	Simpson - TD	3464
		3771
		4118

**RECEIVED**  
 STATE CORPORATION COMMISSION

JUL 13 1964

CONSERVATION DIVISION  
 Wichita, Kansas

The undersigned, Gerald W. Pike, ~~MEMBER~~ <sup>Partner</sup> for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By Gerald W. Pike ~~MEMBER~~ <sup>Partner</sup>

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } ss.:

On this 2th day of July, 19 64, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared Gerald W. Pike, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its ~~MEMBER~~ <sup>Partner</sup> and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966.

Maxine Blackman  
 Maxine Blackman Notary Public