


15-155-02648-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Reno County, Sec. 26 Twp. 23 Rge. 4 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines W/2 W/2 NW  
Lease Owner S & R Oil Co. P O Box 559  
Lease Name E. Krebbiel Well No. B-3  
Office Address Tulsa, Oklahoma 74101  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 12-1-1935  
Application for plugging filed Feb. 5th 1971  
Application for plugging approved Feb. 8 8th 1971  
Plugging commenced 19  
Plugging completed April 21 1971  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation Mississippi Depth to top Bottom 3499 Total Depth of Well 3618 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 16"    | 251    | None       |
|           |         |      |    | 7"     | 3590   | 548'2"     |
|           |         |      |    | 5 1/2" | 3201   | 2496.60    |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set rock bridge at 3200' and dumped 5 sacks of cement. Shot pipe off at 2496.60'. Pulled pipe and mudded hole to 225". Set rock bridge from 225' to 200' and finished filling hole with 6 yards of ready mix cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1971  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Bert Self  
Address Hutchinson, Kans.

STATE OF Kans., COUNTY OF Reno, ss.  
Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self  
R. R. #4, Hutchinson, Kans. 67501  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of April, 1971



Notary Public





# WELL RECORD — (Continued)

WELL NO. B-3

LEASE E. Krehbiel "B"

**(12) ADDITIONAL INFORMATION**

**(13) MATERIAL LOST IN HOLE**

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 3 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

**(14)**

## WELL LOG

| FORMATION             | FROM | TO   | NO. OF FEET | DRILL. TIME | FORMATION         | FROM | TO   | NO. OF FEET | DRILL. TIME |
|-----------------------|------|------|-------------|-------------|-------------------|------|------|-------------|-------------|
| Sand                  | 0    | 140  |             |             | Shale & shells    | 2355 | 2405 |             |             |
| Sand & clay           |      | 180  |             |             | Lime & shale      |      | 2450 |             |             |
| Sand                  |      | 188  |             |             | Lime              |      | 2735 |             |             |
| Shale                 |      | 245  |             |             | Broken lime       |      | 2752 |             |             |
| Shale & lime shells   |      | 422  |             |             | Lime              |      | 2936 |             |             |
| Shale                 |      | 495  |             |             | Shale & lime      |      | 2964 |             |             |
| Lime                  |      | 570  |             |             | Lime              |      | 3050 |             |             |
| Broken lime           |      | 672  |             |             | Shale & lime      |      | 3061 |             |             |
| Shale, anhydrite      |      | 780  |             |             | Lime & shale      |      | 3137 |             |             |
| Lime                  |      | 820  |             |             | Shale             |      | 3206 |             |             |
| Broken lime & shale   |      | 844  |             |             | Shale, var.       |      | 3247 |             |             |
| Broken lime           |      | 925  |             |             | Chert             |      | 3366 |             |             |
| Red rock              |      | 937  |             |             | Lime              |      | 3577 |             |             |
| Lime & shells & shale |      | 986  |             |             | Chert             |      | 3593 |             |             |
| Shale & shells        |      | 995  |             |             | Chert, lime       |      | 3405 |             |             |
| Lime                  |      | 1059 |             |             | Lime              |      | 3494 |             |             |
| Red rock              |      | 1070 |             |             | Broken lime       |      | 3497 |             |             |
| Lime                  |      | 1134 |             |             | Shale             |      | 3600 |             |             |
| Shale & shells        |      | 1372 |             |             | Sand, R. U. S. T. |      | 3602 |             |             |
| Shale                 |      | 1477 |             |             | Lime              |      | 3615 |             |             |
| Shale & shells        |      | 1570 |             |             | Sandy lime, T. D. |      | 3618 |             |             |
| Shale & lime          |      | 1628 |             |             |                   |      |      |             |             |
| Shale & shells        |      | 1785 |             |             |                   |      |      |             |             |
| Shale & lime          |      | 1850 |             |             |                   |      |      |             |             |
| Shale & shells        |      | 1935 |             |             |                   |      |      |             |             |
| Shale & lime          |      | 1985 |             |             |                   |      |      |             |             |
| Lime                  |      | 2081 |             |             |                   |      |      |             |             |
| Lime & shale          |      | 2136 |             |             |                   |      |      |             |             |
| Lime                  |      | 2201 |             |             |                   |      |      |             |             |
| Broken lime           |      | 2239 |             |             |                   |      |      |             |             |
| Lime & shale          |      | 2355 |             |             |                   |      |      |             |             |