


Give information completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway,
 Wichita, Kansas

WELL PLUGGING RECORD

15-095-01242-0000

NORTH



Locate well correctly on above Section Plat

Kingman County. Sec. 1 Twp. 27S Rge. (E) 8W (W)
 Location as "NE/CNW/SW" or footage from lines. G-NW-SW
 Lease Owner Sunray DX Oil Company
 Lease Name Lucy Stucky Well No. 2
 Office Address 321 West Douglas, Wichita 2, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed 19____
 Application for plugging filed May 2, 19 62
 Application for plugging approved May 3, 19 62
 Plugging commenced May 11, 19 62
 Plugging completed May 12, 19 62
 Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred Hampel, Pretty Prairie, Kansas
 Producing formation Lansing Kansas City Depth to top 3286' Bottom 3308' Total Depth of Well 3750' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City	Water	3286'	3308'			
		0	277'	8 5/8"	277'	-0-
		0	3734'	4 1/2"	3734'	3185'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3750' to 3650'. Dumped 5 sacks of cement from 3650' to 3590'. Filled hole with mud from 3590' to 260'. Set rock bridge at 260'. Dump 20 sacks of cement from 260' to 200'. Mud from 200' to 40' and set rock bridge at 40'. Dump 10 sacks of cement from 40' to top of surface pipe.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 15 1962
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Forbes Casing Pulling Company
 Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
 Gary W. Pierce (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary W. Pierce
 321 West Douglas, Wichita 2, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of May, 19 62

My commission expires July 13, 1963 Notary Public.



15-095-01242-0000

DRILLER'S WELL LOG

OPERATOR: SUNRAY MID-CONTINENT OIL COMPANY WELL NAME: LUCY STUCKY #2
 LOCATION: C NW SW 1-27S-8W
 Kingman County, Kansas

CONTRACTOR: K & E DRILLING, INC.
 719 UNION CENTER BLDG.
 WICHITA, KANSAS

CASING RECORD: 8 5/8" @ 277' w/ 300 sx.
 4 1/2" @ 3739' w/ 100 sx.

ROTARY TOTAL DEPTH: 3750'

COMMENCED: 4-16-62
 COMPLETED: 4-25-62
 ELEVATION: 1608 KB
 PRODUCTION: 1605 DF
 None

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Sand	30
Red Bed	280
Shale	1490
Shale & Lime	1975
Shale	2215
Shale & Lime	2840
Lime	3090
Shale	3275
Lime	3750

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 10 1962
 CONSERVATION DIVISION
 Wichita, Kansas

CERTIFICATION

State of KANSAS }
 County of SEDGWICK } ss:

I, H. L. Wilson, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

H. L. Wilson

Subscribed and sworn to before me this 9th day of May H. L. Wilson 62

Patsy A. Roberts

Notary Public.

My Commission expires: April 17, 1966 Patsy A. Roberts

