

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-20766-0000

LEASE NAME Stucky

WELL NUMBER A-1

 Ft. from S Section Line

 Ft. from E Section Line
NW SW NE

SEC. 1 TWP. 27S RGE. 8W (E) or (W)

COUNTY Kingman

Date Well Completed

Plugging Commenced 6-24-93

Plugging Completed 6-29-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Jay C. Boyer

ADDRESS Box 511 Hays, Kansas 67601

PHONE# (913) 625-6967 OPERATORS LICENSE NO. 6139

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Jack Iuthi (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3669'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	276'	none
				4-1/2"	3668'	2700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand to 3500' and 4 sacks cement. Shot pipe @ 3100', 2900', 2800', 2700', pulled up to 1150' and pumped 35 sacks cement, pulled to 750' and pumped 35 sacks cement, pulled to 350' and circulated cement to surface.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jay C. Boyer

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 8th day of July **RECEIVED**
STATE CORPORATION COMMISSION

Jane Herzberg
Notary Public

JUL - 9 1993

My Commission Expires:



CONSERVATION DIVISION
REVISED 2-25-88

15-095 207 66-0000

EMPHASIS OIL OPERATIONS

P. O. Box 506
Russell, Kansas 67665

DRILLERS LOG

OPERATOR: Jay C. Boyer
Box 511
Hays, KS 67601

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Stucky "A" WELL: #1

LOCATION: NW SW NE
Section 1-27S-8W
Kingman County, Kansas

Total Depth: 3669'

Elevation:

Commenced: 11-22-78

Completed: 11-29-78

Casing: 8-5/8" @ 276'
4-1/2" @ 3668'

Status: Oil Well

DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand & Shale	303	Lime & Shale	3433
Shale & Shells	1240	Lime & Chert	3508
Shale	1680	Lime (R.T.D.)	3669
Shale & Lime	3098		

STATE OF KANSAS)
COUNTY OF RUSSELL) ss

I, Joe K. Branum, of Emphasis Oil Operations state that the above and foregoing is a true and correct log of the above captioned well.

Joe K. Branum

Joe K. Branum

Subscribed and sworn to before me this 4th day of December, 1978.
My Commission Expires: October 2, 1979.

Patricia Clark

Notary Public

