

15-095-213000000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Kingman SEC. 1 TWP. 27 RGE. 8 E/W
 Location as in quarters or footage from lines:
C S/2 S/2 NW/4

Lease Owner Jay C. Boyer
 Lease Name Stucky C Well No. 5
 Office Address Box 511 Hays, Kansas 67601
 Character of Well (Completed as Oil, Gas or Dry Hole):
 Date Well Completed 11-16-82
 Application for plugging filed 11-16-82
 Plugging commenced 11-16-82
 Plugging completed 11-16-82
 Reason for abandonment of well or producing formation

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Glenn Ward
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3683'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out.

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Bottom Plug: @ 220' w/30 sacks 50/50 pozmix 4% gel 3% cc. thru drill pipe
 Top Plug: @ 40' w/solid bridge & 10 sacks cement
 10 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.
Bill Draney (employee of owner) or ~~(owner or operator)~~ of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Bill Draney
Box 823 Great Bend, KS 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 18 day of November, 1982

RECEIVED
 STATE CORPORATION COMMISSION
M. Mague
 Notary Public.

My Commission expires: 4-29-86

NOV 24 1982

15-095-213000000

DRILLERS' WELL LOG

DATE COMMENCED: November 11, 1982
DATE COMPLETED: November 17, 1982

Jay C. Boyer
STUCKY C-5
C S/2 S/2 NW/4
Sec. 1, T27S, R8W
Kingman County, Ks.

ELEVATION: 1608 K.B.

0 - 2834' Surface Soil, Sand, Red Bed,
Shale & Lime
2834 - 3061' Lime
3061 - 3072' Shale & Lime
3072 - 3089' Lime
3089 - 3278' Shale
3278 - 3290' Lime & Shale
3290 - 3683' Lime
3683' RTD

FORMATION DATA

Topeka 2834'
Heebner 3061'
Toronto 3072'
Douglas 3089'
Br. Lime 3278'
Lansing K.C. 3290'
RTD 3683'

Surface Pipe: Set new 8-5/8",
20# pipe @206' w/200 sacks
50/50 pozmix, 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and
statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 18 day of November 1982.

My Comm. Expires:

4-29-86

Alonzo M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

NOV 24 1982

CONSERVATION DIVISION
Wichita, Kansas