

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-095-21,348

LEASE NAME ELDER

WELL NUMBER 1

SPOT LOCATION C N/2 SW SW

SEC. 1 TWP. 27 RGE. 8 (E) OR (W)

COUNTY Kingman

DATE WELL COMPLETED 7-25-83

PLUGGING COMMENCED 7-25-83

PLUGGING COMPLETED 7-25-83

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Jay C. Boyer

ADDRESS P.O. Box 511 Hays, KS 67601

PHONE # (913) 625-6967 OPERATORS LICENSE NO. 6139

CHARACTER OF WELL D & A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Morris Leslie, Nashville, Ks.

IS ACC-1 FILED? to be filed by operator IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 3685'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Bottom Plug: @ 650' w/35 sacks 60/40 pozmix, 4% gel 3% cc. thru drill pipe
Middle Plug: @ 250' w/35 " " " " " " " "
Top Plug: @ 60' w/25 sacks cement thru Drill pipe
10 sacks cement in Rat Hole

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Duke Drilling Co., Inc. LICENSE No. 5929
ADDRESS P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, SS.

Bill Draney (EMPLOYEE OF OPERATOR) OR
~~OPERATOR~~ OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT, SO HELP ME GOD.

(SIGNATURE) Bill Draney

(ADDRESS) P.O. Box 823 Great Bend, KS

SUBSCRIBED AND SWORN TO BEFORE ME THIS 27 DAY OF July, 1983

[Signature]
NOTARY PUBLIC

RECEIVED
STATE CORPORATION COMMISSION

MY COMMISSION EXPIRES: 4-29-86

AUG 05 1983

REGISTRATION DIVISION
WICHITA, KANSAS

FORM CP-4
REVISED 06-83

DRILLERS' WELL LOG

15-095-21348-0000

DATE COMMENCED: July 20, 1983
DATE COMPLETED: July 25, 1983

Jay C. Boyer
ELDER #1
C N/2 SW SW
Sec. 1, T27S, R8W
Kingman County, Ks.

ELEVATION: 1615 K.B.

0 - 2774' Surface Soil, Sand, Red Bed,
Shale
2774 - 3031' Lime
3031 - 3035' Shale
3035 - 3063' Lime
3063 - 3247' Shale
3247 - 3268' Lime & Shale
3268 - 3685' Lime
3685' RTD

FORMATION DATA

Topeka = 2774'
Heebner 3031'
Douglas 3063'
Br. Lime 3247'
Lansing K.C. 3268'
RTD 3685'

Surface Pipe: Set new 8-5/8",
20# pipe @ 206' w/150 sacks
60/40 pozmix, 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and
statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 27 day of July 1983.

My Comm. Expires:

4-29-86

Dorothy M. Hagre
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

AUG 05 1983

CONS. DIV. OF STATE
WICHITA, KANSAS