

15-095-20477000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County, Sec. 5 Twp. 27 Rge. 9 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
C SW NW

Lease Owner Fickerell Drilling Company
Lease Name Knoppenberger A#1 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8/9/76 _____ 19____
Plugging completed 8/17/76 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4330
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	217	none
				4 1/2"	3709	2257

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, ran sand to 3600' and dumped 4 sacks cement. Shot pipe at 3053', spotted 40 barrels oil behind pipe. Shot pipe at 2971', 2607', 2410', 2249', 2084', worked pipe loose at 2249', pulled 56 joints of range 3 pipe. Plugged well with 2 sacks hulls, 10 sacks gel and 100 sacks common cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1976

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

(Address)

Subscribed and sworn to before me this 23rd day of August, 19 76

NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

Margaret Melcher
Notary Public.

ROTARY DRILLING LOG

15-095-20477-0000

COMPANY: PICKRELL DRILLING COMPANY
205 LITWIN BLDG.
WICHITA, KANSAS 67202
LOCATION: KNAPPENBERGER "A" #1
C SW NW Sec. 5-27S-9W
Kingman, Kansas

Rotary Drilling Commenced 4-10-76
Rotary Drilling Completed 4-23-76

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Set 8 5/8" casing at 217' KB w/150 sx.
Set 4 1/2" casing at 3709' w/125 sx.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Top soil	180	Lime	4330
Red Beds	218		
Red Beds	250		
Red Bed & Shale	1130		
Shale	1540		
Shale & Lime	1790		
Lime & Shale	1950		
Lime & Shale	2080		
Shale & Lime	2235		
Lime & Shale	2385		
Lime & Shale	2520		
Shale & Lime	2630		
Shale & Lime	2745		
Shale & Lime	2890		
Shale & Lime	3050		
Shale & Lime	3225		
Shale & Lime	3320		
Shale & Lime	3412		
Lime	3440		
Lime	3530		
Lime	3578		
Lime & Shale	3630		
Lime & Shale	3654		
Lime	3685		
Lime	3702		
Lime & Shale	3785		
Lime	3837		
Lime	3910		
Lime	3957		
Lime	3973		
Lime	3993		
Shale & Lime	4160		
Lime & Shale	4220		
Lime & Shale	4232		
Lime & Shale	4260		
Lime	4314		

RECEIVED
STATE OF KANSAS COMMISSION
JUN 02 1976
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
Attorney-in-Fact
C. W. Sebitts

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 1 day of June, 1976, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires:



[Signature]
Notary Public
Jo Ann Sarver