


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kingman County, Sec. 5 Twp. 27S Rge. 9W /#/#  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
E/2 NE/4 NE/4  
Lease Owner Gear Petroleum Company  
Lease Name Schumacher Well No. 1  
Office Address 1325 Vickers KSB&T Bldg., Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

D & A  
Date Well completed May 31, 1978  
Application for plugging filed May 31, 1978  
Application for plugging approved May 31, 1978  
Plugging commenced May 31, 1978  
Plugging completed May 31, 1978  
Reason for abandonment of well or producing formation

D & A  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Jasper H. Metz  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 14,213  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200.36'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug @ 210' w/40 sx cement  
Plug @ 40' w/12 sx cement

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 0 9 1978 06-08-78  
CONS. DIVISION OF KANSAS  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company  
1720 KSB&T Building, Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick, ss. contractor  
Gloria Fawcett (employee of ~~xxxxxxx~~)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett  
1720 KSB&T Building, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of June, 1978.

My commission expires \_\_\_\_\_

Joyce A. Hagermann  
Notary Public.



DRILLERS LOG

15-095-20717-0000

No. 1 Schumacher

CASING RECORD: 8 5/8" @ 209.76' w/175 sx cement

COMPANY: Gear Petroleum Company

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: May 20, 1978

COMPLETED: May 31, 1978

DESCRIPTION: E/2 NE/4 NE/4 Sec. 5-T27S-R9W Kingman County, Kansas

TOTAL DEPTH: 4,213'

ELEVATION: 1,713' KB

FORMATION	FROM	TO	REMARKS
Surface Soil & Clay	0	30	
Sand	30	174	
Red Bed	174	280	
Shale w/Red Bed	280	377	
Red Bed & Gray Shale	377	925	
Shale	925	1244	
Salt, Lime & Shale	1244	1420	
Lime w/Shale	1420	1466	
Shale w/Lime	1466	1490	
Lime w/Shale	1490	1676	
Lime & Shale	1676	2649	
Lime	2649	2740	
Lime & Shale	2740	2872	
Lime	2872	2960	
Lime & Shale	2960	3260	
Lime	3260	4022	
Kinderhook Shale	4022	4076	
Gummy Shale & Lime	4076	4140	
Lime & Shale	4140	4213	
RTD		4213	

RECORDED  
 JUN 08 1978  
 COUNTY CLERK'S OFFICE  
 SEDGWICK COUNTY, KANSAS

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

*Gloria Fawcett*  
 Gloria Fawcett

Subscribed and sworn to before me this 6th day of June, 1978.

*Joyce A. Hagermann*

