

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. 5 TWP. 27S RGE. 9W ~~E4W~~
Location as in quarters or footage from lines:
NE SE NE

Lease Owner Kiowa Exploration Company
Lease Name Schumacher Well No. 1
Office Address 610 Hardage Center, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed July 25, 1983
Application for plugging filed July 25, 1983
Plugging commenced July 25, 1983
Plugging completed July 25, 1983
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Van Gieson
Producing formation _____ Depth to top _____ bottom T.D. 4211 ✓

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	shale	0	262	8-5/8"	258	none
	cemented with 225 sx common, 2% gel, 3% cc, plug down at 1:15 p.m. 7-17-83 by Halliburton; cement did circulate					

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged as follows with 60/40 posmix 2% gel, 3% cc
35 sx @ 900'; 35 sx @ 300'; 25 sx @ 60' 10 sx in rat hole; no bridge
plug required per state plugger; plug down at 2 p.m. by
Halliburton 7-25-83.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. W. Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Jon T. Williams, Jr. (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

RECEIVED (Signature) Jon T. Williams, Jr.
STATE CORPORATION COMMISSION 200 E. First, Suite 500, Wichita, KS
(Address)



III 29 1983
TO before me this 25th day of July, 19 83

Geraldine Stewart
Geraldine Stewart Notary Public.

My Commission expires: January 14, 1985