


15-151-00269-000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

PRATT County. Sec. 28 Twp. 27 Rge. 11 (E) 11 (W)
Location as "NE/CNW&SW" or footage from lines NW NE NW
Lease Owner GRAHAM-MESSMAN-RINEHART OIL COMPANY
Lease Name FATRCHILDS "A" Well No. 11
Office Address 1005 EAST SECOND STREET, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed MAY 8, 1954 19
Application for plugging filed MAY 8, 1954 (Verbal) 19
Application for plugging approved MAY 8, 1954 (Verbal) 19
Plugging commenced MAY 8, 1954 19
Plugging completed MAY 8, 1954 19
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well M. A. RIVES, BOX 8 PRATT, KANSAS
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 4550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	208'	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from --- feet to --- feet for each plug set.

SET BOTTOM PLUG AT 208 FEET
WITH 1/2 SACK HULLS AND 30
SACKS CEMENT. FILLED WITH
MUD TO 20 FEET, SET SECOND
PLUG WITH 1/2 SACK HULLS AND
AND 15 SACKS CEMENT. MUD TO
SURFACE.

RECEIVED
STATE CORPORATION COMMISSION
05-12-54

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GRAHAM-MESSMAN-RINEHART OIL COMPANY
Address 1005 EAST SECOND STREET, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. A. GILLILAND (employee of owner) or (SWORN OFFICER) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
1005 EAST SECOND STREET, WICHITA, KS.
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 1954

Betty June Bayles
Notary Public.

My commission expires SEPTEMBER 14, 1957

PLUGGING
FILE SEC 28 TWP 27 R 11 W
BOOK PAGE 33 LINE 11

NO. 1 FAIRCHILD'S "A"

WELL RECORD

Location: NW NE NW, 28-27S-11W
Pratt County, Kansas

Operator: Graham-Messman-Rinehart Oil Company
1005 E. 2nd St., Wichita, Kansas

Contractor: Graham-Messman-Rinehart Oil Company
1005 E. 2nd St., Wichita, Kansas

Casing Record: 13 3/8" @ 208' W/250 sacks cement

Commenced: April 24, 1954

Completed: May 8, 1954

Elevation: 1803 K.B.

Production: D & A

LOG

Clay	36
Sand	177
Shale (red)	208
Shale	470
Shale	700
Shale	1495
Shale	1693
Shale-lime	1860
Shale-lime	2110
Lime-shale	2305
Shale-lime	2530
Lime-shale	2835
Shale-lime	3045
Lime-shale	3405
Shale-lime	3590
Lime-shale	3688
Lime	3743
Lime-shale	3775
Lime	3857
Lime	3939
Lime	4110
Lime	4148
Lime-chert	4178
Lime	4298
Shale-lime-chert	4340
Lime	4371
Viola chert-lime	4376
Lime	4436
Simpson	4527
Arbuckle	4550 R.T.D.

TOPS

Heebner	3451' (-648)
Brown lime	3628' (-1925)
Lansing	3648' (-1845)
Mississippi	4115' (-2312)
Kinderhook	4219' (-2416)
Viola	4329' (-2526)
Arbuckle	4518' (-2715)

The undersigned, GRAHAM-MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well, as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me this 11 day of May, 1954.

Beiter June Boyles
Notary Public

My Commission Expires: September 14, 1957

PLUGGING
PRK SEC 28-27-11W
BOOK PAGE 33 LINE 11