

State Corporation Commission
Wichita State Office Bldg.
130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-20,794-0001

LEASE NAME Murphy

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 23 TWP. 27S RGE. 10W (E or W)

COUNTY Kingman

Date Well Completed

Plugging Commenced 10-24-94

Plugging Completed 10-27-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

EASE OPERATOR Chew Oil & Gas Co.

ADDRESS 117 W. Main P.O. Box 90 Lyons, Kansas 67554

PHONE (316) 257-5587 OPERATORS LICENSE NO. 6153

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Van Gieson (XCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4404'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	218'	none
				5 1/2"	4393'	3503.95

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging materials used, state the character of same and depth placed, - from feet to feet each sack. Sanded bottom to 3950', cemented bottom with 5 sacks cement. Shot @3504'. Loaded hole and mixed 35 sacks @1350', 35 sacks @980' pulled casing to 270' and circulated cement to surface w/90 sacks pulled casing and topped off w/10 sacks 60/40 4% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 2537

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chew Oil & Gas Co.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed therewith. The same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 2 day of November, 19 94

Irene Herzberg
Notary Public

IRENE HERZBERG
State of Kansas
My Appt. Exp. Aug. 24, 1997

USE ONLY ONE SIDE OF EACH FORM
My Commission Expires:

RECEIVED
STATE CORPORATION COMMISSION
NOV 02 1994
WICHITA, KANSAS