

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 5 095-21663-0000

LEASE NAME Bayer

WELL NUMBER 7

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 24 TWP. 27 RGE. 10 ~~XXXX~~ (W)

COUNTY Kingman

Date Well Completed _____

Plugging Commenced 11/13/96

Plugging Completed 11/14/96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mach Petroleum, Inc.

ADDRESS P.O. Box 35583, Tulsa, OK 74156

PHONE# (316) 596-2676 OPERATORS LICENSE NO. 30146

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/13/96 (date)

by Jack Luthie (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Miss Depth to Top 4028 Bottom 4042 T.D. 4460

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	313	None
				5 1/2	4459	2200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s Set CTBP at 3875, dump 2sx portland cement with dump bailer, stretch and cut pipe at 2200, pull casing to 1455, spot 35sx, pull to 960, spot 35sx, pull to 358 and circulate cement to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mach Petroleum Inc.


STATE OF Kansas COUNTY OF Barber, ss. 11-19-96

Alan Vratil (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 15 day of November, 1996

Glenda Morrison
Notary Public

My Commission Expires: 10/14/98