


15-095-01527-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Kingman County, Sec. 24 Twp. 27 Rge. 10 ~~(E) (W)~~  
 Location as "NE/CNW/SW" or footage from lines NE NW NW  
 Lease Owner Anderson-Prichard Oil Corporation  
 Lease Name Bayer Well No. 1  
 Office Address Box - 142 Great Bend, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed August 17, 19 51  
 Application for plugging filed October 12, 19 51  
 Application for plugging approved October 13, 19 51  
 Plugging commenced October 17, 19 51  
 Plugging completed November 9, 19 51  
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkea  
 Producing formation Depth to top Bottom Total Depth of Well 4322 Feet  
 Show depth and thickness of all water, oil and gas formations. PB3825

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	288'	none
				5-1/2	4141'	1660'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock & 6 sax cement to 3802'  
 Shot Casing Off at 1660'- Pulled Casing  
 Filled with heavy mud to 280'  
 Set Bridge and dumped 15 sax cement w/bailer  
 Filled hole with heavy mud to 30' of top  
 Mixed 10 sax cement for bridge cap on well

NOV 28 1951  
 CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
 Correspondence regarding this well should be addressed to W. J. Dearen % Anderson-Prichard Oil Corp.  
 Address Box 142 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
 Gerald M. Dougherty (employee of owner) or (owner or operator) of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Gerald M. Dougherty*  
 Box 142 - Great Bend, Kansas  
 (Address)

SUBSCRIBED AND SWORN to before me this 27th day of November, 19 51

*Verselle M. Jenkins*  
 Notary Public.

My commission expires December 4, 1954

PLUGGING  
 FILE SEC 24T 27 R 100  
 BOX PAGE 14 LINE 20

1509501527-000

BAYER #1 WELL

LOCATION: NE $\frac{1}{4}$  NW $\frac{1}{4}$  NW $\frac{1}{4}$  Sec. 24-27-10<sup>W</sup>  
Kingman County, Kansas

OPERATOR: Anderson-Prichard Oil Corp.

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: 289' of 24# 8-5/8" casing cemented  
at 288' with 250 sacks cement and 2 c.c.

OIL STRING: Ran 4143.59' 5 $\frac{1}{2}$ " O.D. 15.5# casing  
cemented at 4141' with 150 sacks cement.

SPUDDED: 7-20-51

COMPLETED: 8-5-51

L O G

(Figures indicate bottom of formation)

0	to	110	Sand
		205	Shale and shells
		288	Red bed
		535	Sand, red bed & shale
		550	Anhydrite
		1350	Shale and shells
		1520	Shale and lime
		1645	Lime
		2350	Shale and lime
		2525	Shale
		2545	Lime
		3500	Lime and shale
		3960	Lime
		4015	Shale and lime
		4030	Lime
		4050	Mississippi Lime
		4090	Cherty lime
		4110	Cherty lime and shale
		4306	Shale
		4322	Shale and lime
		4322	Total Depth.

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Bayer #1 well as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

BY Richard Hindery

Subscribed and sworn before me  
this 7th day of August, 1951.

Virman J. Genger  
Notary Public

My commission expires November 29, 1954.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 13 1951

PLUGGING  
FILE SEC 24-27-10  
BOOK PAGE 116 LINE 20

PLUGGING  
FILE SEC 24-27-10  
BOOK PAGE 116 LINE 20