

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

4- November RECEIVED  
FILED

STATE CORPORATION COMMISSION

NOV 10 1931

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-047-20,952

Dear Sir:

Mr. Jim Shriner of Stirling Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: S. E. Hall

Complete Address: 6427 East Kellogg Wichita Kansas 67202

Lease Name: Johnson Well No. 2-5

Location: 1320' FSL-990' FEL of SW 1/4 Sec. 5 Twp. 24S Rge. 17W (E) (4)

County: Edwards Total Depth: 4520'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Shriner was instructed to plug the well as follows:

There is 251' of 8 1/8" surface casing cement circulated. They taped the collar hole at 700' and bottomed at 860'. The anhydrite was at 1178'. 1st plug with hole full of heavy mud was at 1100' with 70 lbs of cement. 2nd plug at 880' with 70 lbs of cement. 3rd plug at 230' with rubber plug pushed to this depth with 30 lbs of cement on top of it. 4th plug at 40'-0' on rubber plug with 10 lbs of cement. They pumped 5 lbs of cement in rat hole & 5 lbs of cement in mouse hole. Plugging accomplished by Halliburton outfit of Great Bend Kans.

Very truly yours,

Paul Luthis  
Conservation Division Agent