

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
OCT 13 1970
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cook _____ of Imperial Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Cook _____ guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Co.

Complete Address: 780 4th Natl Bank Bldg. Wichita, Ks

Lease Name: Doll _____ Well No. 1

Location: 300 ft SE of C NE/4 _____ Sec. 5 Twp. 24s Rge. 16 (E)(W) _____

County: Edwards _____ Total Depth 4345 Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A Lost Hole _____

Mr. Cook _____ was instructed to plug the well as follows:

317 ft of 8 5/8 surface pipe cemented with 300 sacks. Pump
50 sacks cement to 650 ft. Fill hole to 250 ft, & 30 sacks
cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement
to surface. 2 sacks cement in rat hole.

Globe Cementing Co. Great Bend, Ks

Very truly yours,

Conservation Division Agent