

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 8 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kansas Exploration Co.

Complete Address: 232 Bonnie Brae, Wichita, Kansas

Lease Name Mead Well No. # 1

Location NW NW NE Sec. 6 Twp. 24 Rge. 16 (E) (W) W

County Edwards Total Depth 4393

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co.

Address: P. O. Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 3:00PM Day 4th Month Feb. Year 1963

The Above well was plugged as follows:

4316' of 5½" long string cemented with 75 sacks, Top of perforation
4249' to 4255'. Sanded to 4240' and cemented with 5 sacks. 228' of
8 5/8" surface pipe, circulated with 175 sacks cement. Fluid in hole
was at 100' level. An over night plug was set at 200' and cemented
with 5 sacks through the bailer. The next morning the fluid would not
bail down in the hole, so a squeeze job was necessary. 15 sacks of mud
and 75 sacks was pumped in hole by Sun Cementing Co. Cemented to cellar
base. 3505' of pipe was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/6/63

INV. NO. 6533-W