

State of Kansas



FORM - CP-2  
Rev. 9-8-64

15-095-30024-0000

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 30 1965  
4-30-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Charles R. King of Stelbar Oil Corp., Inc. has this date requested permission to plug the following described well:

Mr. King guarantees payment of the plugging fee.

Operator's full Name: Stelbar Oil Corporation, Inc.

Complete Address: 310 Petroleum Bldg., Wichita, Kansas

Lease Name: Henning "A" Well No. # 1

Location: 150' W of C NW SW Sec. 19 Twp. 28 Rge. 7 (E) (W) W

County Kingman Total Depth 4463' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. King was instructed to plug the well as follows:

278' of 8 5/8" surface pipe, cement circulated with 250 sacks.  
Fill hole with drilling mud to 265', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent