



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burton of Pickrell Drlg. Co. has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 Fourth Nat'l Bank Bldg., Wichita, Kansas

Lease Name: Strowitz "A" Well No. 1

Location: C SE SE Sec. 6 Twp. 24 Rge. 21 (E) (W)

County: Hodgeman Total Depth 4685' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Burton was instructed to plug the well as follows:

8 5/8" To 255' circulated w/ cement. Mud 4685' to 800'.

Spot 80 sacks cement 800' to 500'. Mud 500' to 250'

Spot 30 sacks cement 250' to 150'. Mud 150' to 45'.

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent