

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. STATE CORPORATION COMMISSION
WICHITA, KANSAS 67202

NOV 8 1972

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of DNB has this

date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.Operator's full Name: DNB DrillingComplete Address: 701 1st Nat'l BK Bldg., Wichita, KansasLease Name: Hardtner Well No. 1Location: C NE NE Sec. 11 Twp. 24 Rge. 21 (E) (W)County: Hodgeman Total Depth 4730' Oil Well Gas Well Input Well SWD Well D & A Lost Hole Mr. Norwood was instructed to plug the well as follows:

8 5/8" to 337' circulated w/ cement. Mud 4730' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 337'

Spot 30 sacks cement 337' to 237' Mud 237' to 45'

Plug, H^ulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent