

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, GWWO, Injection. Type and complete ALL sections.

Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic-log, gamma ray neutron log, etc.). KCC # (315) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Wildcat Resources

API NO. 095-21,224-0000

ADDRESS Rt. # 3 Hillsboro, Kansas 67063

COUNTY Kingman

FIELD CASLEY

**CONTACT PERSON Merle Schlehuber PHONE 316-947-2343

PROD. FORMATION MISSISSIPPI

LEASE Tip Top Credit Union

PURCHASER

WELL NO. 3

ADDRESS

WELL LOCATION NE NE SW

DRILLING Contractor Kansas Drilling & Well Serv., Inc.

330 Ft. from NORTH Line and

CONTRACTOR ADDRESS Box 254

330 Ft. from EAST Line of

ADDRESS Marion, Kansas 66861

the SEC. 2 TWP. 28 RGE. 5W

WELL PLAT

PLUGGING CONTRACTOR ADDRESS

RECEIVED STATE CORPORATION COMMISSION

WELL PLAT grid diagram showing a 4x4 grid with a crosshair in the center.

KCC KGS (Office Use)

TOTAL DEPTH 4400' PBTD

CONSERVATION DIVISION Wichita Kansas

SPUD DATE 2-15-82 DATE COMPLETED 3-1-82

ELEV: GR 1416 DF KB 1424

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 260'KB DV Tool Used? NO

AFFIDAVIT

STATE OF Kansas, COUNTY OF Marion, SS, I,

Merle Schlehuber OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS a representative (FOR) (OF) Wildcat Resources

OPERATOR OF THE Tip Top Credit Union LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 3 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 1 DAY OF June, 19 82, AND THAT


ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

SUBSCRIBED AND SWORN BEFORE ME THIS 1st DAY OF June, 19 82.

(S) Merle Schlehuber

Carolyn Kleiber NOTARY PUBLIC



MY COMMISSION EXPIRES:

**The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

MERLE SCHLEHUBER 316-947-2343

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cased intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
0-150 sand, lime, shale				
150-2976 lime, shale				
2976-3025 Lans				
3025-3790 K.C.				
3790-3935 Miss				
3935-4080 Miss lime				
4080-4214 Kinderhook				
4214-4215 Viola				
4215-4287 Simpson				
4287-4400 Arbuckle				
4400 TD				

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8 5/8"		260' KB	Class A Common	160	3% CACL
Production		5 1/2"		4325' KB	60-40 Pozmix	200	5 lb. Gilsonite/sax 30 bbl. salt flush

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
			2		3779-83
			2		3789-93

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 GAL. 15% M.C.A.	3779-83
	3789-93

Date of first production TEST June 2, 1982	Producing method (flowing, pumping, gas lift, etc.) SWAB	Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil NONE bbls.	Gas 80 MCF
	Water % 150 bbls.	Gas-oil ratio
Disposition of gas (vented, used on lease or sold)		Perforations AS ABOVE