

CORRECTED ACO-1  
AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.


OPERATOR Woodman-Iannitti Oil Co. API NO. 15-095-21,106-0000  
 ADDRESS 1008 Douglas Building COUNTY Kingman  
Wichita, Kansas 67202 FIELD Broadway Ext.  
 \*\*CONTACT PERSON K. T. Woodman LEASE Twitmeier  
 PHONE (316) 263-6755

PURCHASER Peoples Natural Gas WELL NO. # 1  
 ADDRESS Suite 748, R.H. Garvey Bldg. WELL LOCATION Approx. C E/2 SE NE  
Wichita, Kansas 67202 1980 Ft. from North Line and  
330 Ft. from East Line of  
 the - SEC. 10 TWP. 28s RGE. 5w

DRILLING CONTRACTOR Brandt Drlg. Co., Inc.  
 ADDRESS 1200 Douglas Bldg.  
Wichita, Kansas 67202

PLUGGING CONTRACTOR Not applicable  
 ADDRESS N/A

TOTAL DEPTH 3845 PBDT 3817  
 SPUD DATE 6/27/81 DATE COMPLETED 8/11/81  
 ELEV: GR 1412DF -- KB 1417



WELL PLAT  
 (Quarter) or (Full) Section - Please indicate.

KCC \_\_\_\_\_  
 KGS \_\_\_\_\_

DRILLED WITH (~~CABLE~~) (ROTARY) (~~XXX~~) TOOLS  
 Report of all strings set - surface, intermediate, production, etc. (New)/(Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		247'		170	
Production	7 7/8"	4 1/2"	10.5	3844'	Common	100	10% Salt sat.

RCWD  
10-07-82

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None	---	---			
TUBING RECORD			3	Jet.	3758-64
Size	Setting depth	Pecker set at			
2 3/8"	3791.16	---			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
1000 Gal. 15% M A; Frac. w/ 20,000 Gal. and 15,000 lbs. sand.	3758.64

TEST DATE:		PRODUCTION	
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity	
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water
	trace	625	10
	bbls.	MCF	bbls.
Disposition of gas (vented, used on lease or sold)	Producing Interval(s)		
sold	3758-64		

\*\* The person who can be reached by phone regarding any questions concerning this information.  
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum \_\_\_\_\_ Depth \_\_\_\_\_  
 Estimated height of cement behind pipe \_\_\_\_\_

DV used? No.

**WELL LOG**

Show all important zones of porosity and contents thereof; core intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST # 1 (1710-1741) 30-30-30-30 REC 230' MW, SIP 711-689 #, FP 46-81, 92-104#	1712		Indian Cave	-295
	2674		Heebner	-1257
	2972		Lansing	-1555
	3193		Kansas City	-1776
DST # 2 (3764-3777), 45-60-60-90 GTS/25", Ga. 100 mcfg in 1 hr., SIP 1111-1080 #, FP 31-31, 41-52#	3412		B/Kansas City	-1995
	3672		Mississippi	-2255
	3845		RTD	-2428

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF KANSAS, COUNTY OF SEDGWICK SS,

K. T. WOODMAN OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS a partner FOR Woodman-Iannitti Oil Company OPERATOR OF THE No. 1 Tweitmeyer LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 11th DAY OF August 19 81, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) K. T. Woodman  
K. T. Woodman

SUBSCRIBED AND SWORN TO BEFORE ME THIS 14th DAY OF January 19 82

Kathryn A. Voigt  
NOTARY PUBLIC  
KATHRYN A. VOIGT

MY COMMISSION EXPIRES: APRIL 20, 1985

AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

ORIGINAL OPERATOR : KAN-EX, INC. \*  
 ADDRESS 800 Bitting Building  
Wichita, Kansas, 67202

API NO. 15-095-21,106-0000  
 COUNTY Kingman  
 FIELD \_\_\_\_\_

\*\*CONTACT PERSON Richard L. Bradford

PROD. FORMATION \_\_\_\_\_

PHONE 316/267-2585  
 WOODMAN-LANNITTI TOOK OVER AS OPERATOR AT CSG. POINT.  
 PURCHASER \_\_\_\_\_

LEASE Twietmeyer


ADDRESS \_\_\_\_\_

WELL NO. 1  
 WELL LOCATION Appx. C W $\frac{1}{2}$  SE $\frac{1}{4}$  NE $\frac{1}{4}$

DRILLING Brandt Drilling Co., Inc.  
 CONTRACTOR 1200 Douglas Building  
 ADDRESS 104 S. Broadway  
Wichita, Kansas 67202

\_\_\_\_ Ft. from \_\_\_\_\_ Line and  
 \_\_\_\_ Ft. from \_\_\_\_\_ Line of  
 the NE $\frac{1}{4}$  SEC. 10 TWP. 28S RGE. 5W

PLUGGING \_\_\_\_\_  
 CONTRACTOR \_\_\_\_\_  
 ADDRESS \_\_\_\_\_



WELL PLAT  
 KCC \_\_\_\_\_  
 KGS \_\_\_\_\_  
 MISC \_\_\_\_\_  
 (Office Use)

TOTAL DEPTH 3845' PBTD \_\_\_\_\_  
 SPUD DATE 6-27-81 DATE COMPLETED 7-7-81  
 ELEV: GR 1412 DF \_\_\_\_\_ KB 1417

DRILLED WITH ~~KANEX~~ (ROTARY) (AIR) TOOLS  
 CASING RECORD

(New) / ~~KANEX~~ casing.

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	247'	Common	175	2% Gel, 3% CaCl
Production	7-7/8"	4-1/2"	10#	3844'			

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		
Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls. Gas _____ MCF Water _____ % Gas-oil ratio _____ CFFB	
Disposition of gas (vented, used on lease or sold)		Perforations

\*\*The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum Surface Sand & Gravel Depth 90'

Estimated height of cement behind Surface Pipe To Surface

DV USED? No

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
Shale and Sand	0	257		
Shale & Gypsum	257	387		
Sand & Shale	387	1047		
Lime	1047	1313		
Shale & Lime	1313	1533		
Lime & Cherty Lime	1533	1763		
Sand & Silty Sand	1763	1793		
Lime	1793	2507		
Lime & Shale	2507	2859		
Shale, black	2859	2868		
Shale & Sandy Shale	2868	3215		
Sand, porous	3215	3263		
Sand and Sandy Shale	3263	3403		
Lime	3403	3528		
Shale, black	3528	3535		
Lime, hard and dense	3535	3807		
Shale, lime	3807	3845		
Rotary Total Depth		3845		

A F F I D A V I T

STATE OF KANSAS, COUNTY OF SEDGWICK SS,

TIMOTHY E. BRANDT OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,  
DEPOSES THAT HE IS VICE PRES., GENERAL MANAGER (FOR) (OF) BRANDT DRILLING CO., INC.  
OPERATOR OF THE TWIEIMEYER LEASE, AND IS DULY AUTHORIZED TO MAKE  
THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON  
SAID LEASE HAS BEEN COMPLETED AS OF THE 7TH DAY OF JULY, 19 81, AND THAT  
ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.  
FURTHER AFFIANT SAITH NOT.

SUBSCRIBED AND SWORN BEFORE ME THIS 10TH DAY OF JULY 19 81.

*(S) Timothy E. Brandt*  
TIMOTHY E. BRANDT



VIVIAN F. YINGER  
RECEIVED  
STATE COMMISSION  
NOTARY PUBLIC

OCT 07 1982  
CONSERVATION DIVISION  
Wichita, Kansas