

KANSAS

a-a-81

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION

API Number 15-047-20,956 NOV 10 1981

200 Colorado Derby Building
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name F. G. Hall

Complete Address 6427 East Kellogg Wichita Kansas 67202

Lease Name Johnson Well-No. 2-5

Location South line of SW 1/4 of the NE of the SW
1320 FSL-990 FEL of SW 1/4 Sec. 5 Twp. 24S Rge. 17W (East) (West)

County Edwards Total Depth 4520'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilling Co.

Address Box 129 Sterling Kansas 67579 License No. _____

Operation Completed: Hour: 10:30 PM Day: 4 Month: November Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 251' of 8 5/8 surface casing cement circulated. They topped
the cedar hill at 700' and bottomed at 860'. The anhydrite was topped at
1178'. 1st plug with hole full of heavy mud was at 1100' with 70 lbs
of cement. 2nd plug at 880' with 70 lbs of cement. 3rd plug at
230' with rubber plug pushed to this depth with 30 lbs ^{cement} on top of it.
4th plug at 40' to 0' on rubber plug with 10 lbs of cement. They pumped 5 lbs
of cement in rat hole + 5 lbs in water well. Plugging accomplished
by Haliburton Co. out of Great Bend Kansas.

I hereby certify that the above plugging instructions were given as herein stated.

NOV 10 1981

Signed: Paul Luthie
Conservation Division Agent

DATE 12-11-81
INV. NO. 8660-W