

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

FEB 8 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Buck Unruh of Southwest Casing Pulling has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Kansas Exploration Co.

Complete Address: 232 Bonnie Brae, Wichita, Kansas

Lease Name: Mead Well No. # 1

Location: NW NW NE Sec. 6 Twp. 24 Rge. 16 (E) (W) W

County Edwards Total Depth 4393 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Unruh was instructed to plug the well as follows:

4316' of 5 1/2" long string cemented with 75 sacks. Top of  
perforation 4249' to 4255'. sanded to 4240'. cemented with  
5 sacks. 228' of 8 5/8" surface pipe. Fill hole with mud to 200',  
10' rock bridge cemented with 20 sacks. Fill hole with mud to  
40'. 10' rock bridge cemented with 10 sacks to base cellar.

Very truly yours,

Archie Elving  
 Conservation Division Agent