

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Morgan of James W. Hershberger has this date requested permission to plug the following described well:

Mr. Morgan guarantees payment of the plugging fee.

Operator's full Name: James W. Hershberger

Complete Address: Wichita, Kansas

Lease Name: Dvorak Well No. 1

Location: C SE SW Sec. 7 Twp. 24 Rge. (E) (W) 21

County Hodgeman Total Depth 4900' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Morgan was instructed to plug the well as follows:

8 5/8"-297' Circulated w/cement.

Mud 4900' to 700' Spotted 25 Sax.cement 700' to 625'

Mud 625' to 290' Spotted 25 Sax.cement 290' to 215'

Mud 215' to 40' Plug, Hulls, 15 Sax.cement 40' to 0

Very truly yours,

Conservation Division Agent