

KANSAS

Form CP-3
Rev. 6-4-68

P

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 185 - 11085 - 0000 (of this well)

Operator's Full Name Petroleum Inc.

Complete Address Box 1447-Great Bend, Ks. 67530

Lease Name Toland "C" Well No. 1

Location NW SW NE Sec. 10 Twp. 25s Rge. 14 (E) (W) W

County Stafford Total Depth 4165

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698-Great Bend, Ks. 67530 License No. 670

Operation Completed: Hour 12:30 Pm. Day 5 Month 11 Year 1979

The above well was plugged as follows:

294' 8 5/8" casing w/200 sax cement. 4 1/2" casing set at 3986' w/300
sax cement. Preforated at 3730'-3760'. Sand back to 3700', top sand w/4
sax mixed cement w/ dump bailer. Pull 2100' 4 1/2" casing- Sun mixed
& pumped 8 sax hulls-25 sax gel-100 sax 50/50 posmix cement w/4% gel
& 3% cc to top of casing. Shut in w/"0" pressure.

RECEIVED
STATE CORPORATION COMMISSION

NOV 07 1979 11-7-79

INVOICED

I hereby certify that the above well was plugged as herein stated

DATE 11-7-79

INV. NO. 0845-w

Signed: [Signature]
Well Plugging Supervisor

CONSERVATION DIVISION
Wichita, Kansas