

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Larry Curtis of Duke Drilling Company has this date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: Leo G. Wetherill Jr.

Complete Address: 2208 Power & Light Bldg., Kansas City 5, Mo.

Lease Name: Piepmeier Well No. # 1

Location: SW SW NW Sec. 17 Twp. 24 Rge. 11 (E) (W) W

County Stafford Total Depth 4039' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Curtis was instructed to plug the well as follows:

285' of 8 5/8" surface pipe, cement circulated with 200 sacks.

Fill hole with drilling mud to 250', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with hulls, and cement with 10

sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent