



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

September 8, 1970

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-155-02662-0000

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: S & K Oil Company

Complete Address: P.O. Box 682, Tulsa, Oklahoma 74101

Lease Name: E. Krehbiel Well No. 5

Location: SE SE NW Sec. 26 Twp. 23 Rge. 4 (E)(W) X

County: Reno Total Depth 3583' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole


Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3375' and cement with 5 sacks cement.

Fill hole with mud to 215'. Set rock bridge from 215' to 200' and

cement hole to base of cellar with 6 yards ready-mix concrete.

Very truly yours,

  
Conservation Division Agent