

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
MAY 2 - 1966
CONSERVATION DIVISION
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)
15-155-60378-0005

April 26, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Fred J. Ayesh of Fred J. Ayesh has this date requested permission to plug the following described well:

Mr. Ayesh guarantees payment of the plugging fee.

Operator's full Name: Fred J. Ayesh

Complete Address: 438 Wetmore Drive, Wichita, Kansas

Lease Name: Base Well No. 1

600' N. of South Line S₁SW₁SE

Location: 575' E. of West Line SE $\frac{1}{4}$ Sec. 26 Twp. 23 Rge. 4 (E) (W) X

County Reno Total Depth 2460' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X OWWO

Mr. Ayesh was instructed to plug the well as follows:

Fill hole with mud to 160'. Set rock bridge from 160' to 150' and

cement hole with 35 sacks through drill pipe. Fill hole with mud to

35'. Set rock bridge from 35' to 25' and cap hole with 15 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent