



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cameron of H-30 Drlg. Co. Inc. has this
date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: Donald T. Ingling

Complete Address: 615 1st Natl Bldg. Wichita, Ks

Lease Name: Leo Stucky Well No. 1

Location: NE/NE Sec. 1 Twp. 27S Rge. 8 (E)(W) W

County: Kingman Total Depth 3690 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cameron was instructed to plug the well as follows:

246 ft 8 5/8 surface pipe cemented with 250 sacks. Fill
hole to 225 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud
to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

[Signature]
Conservation Division Agent