



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 20 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Sept 13, 1965.

Dear Sir:

Mr. Ralph Watson of Knight Caseing Pulling Co. has this date requested permission to plug the following described well:

Mr. Watson guarantees payment of the plugging fee.

Operator's full Name: Shallow Water Refining Co.

Complete Address: 1325 Plaza Building Wichita, Kansas.

Lease Name: Bartholomew Unit Tract 17 Well No. #1

Location: C of E<sup>1</sup>/<sub>2</sub>-NE-NE Sec. 1 Twp. 28 Rge. 5 (E) (W) X

County Kingman Total Depth 3768' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Watson was instructed to plug the well as follows:

3768 Ft. 5 1/2" long string perforated 3731-to 3735. Sand to  
3730 & 5 sacks cement. 197ft. of 8 5/8" surface pipe circulated  
with cement. Hole filled with mud to 175 ft. 10 ft. rock bridge  
and 20 sacks cement. Hole filled with mud to 40 ft. 10 ft. rock bridge  
and 10 sacks cement. to base of cellar.

Very truly yours,

*Harmon Justice*  
 Conservation Division Agent