

State of Kansas



15-095-19127-000 FORM - CP-2
Rev. 6-26-62

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Red Bishop of Leben Drilling Inc. has this date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Martin & Kellar

Complete Address: 713 Kennedy Bldg., Tulsa, Oklahoma

Lease Name: Harding Well No. # 1

Location: C W/2 NE Sec. 1 Twp. 28 Rge. 5 (E) (W) W

County Kingman Total Depth 1767 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bishop was instructed to plug the well as follows:

218' of 8 5/8" surface pipe, cement circulated with 175 sacks.

Fill hole with drilling mud to 215', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with

2 sacks.

Very truly yours,

Archie Elving