

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,361-0000

LEASE NAME F. Massey

WELL NUMBER #4-3

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 3 TWP. 24 RGE. 17 (E) or (W)

COUNTY Edwards

Date Well Completed Aug. 16, 1990

Plugging Commenced 4:30AM 8-16-90

Plugging Completed 6:30AM 8-16-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl Company

ADDRESS PO Box 780167, Wichita, Kansas 67278-0167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well dry hole

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 15, 1990 (date).

by Glenn Barlow, Dodge City, Kansas (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	317'KB	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
filled hole with heavy mud. Plugged with 50 sacks at 1170', 40 sacks at 580', 50 sacks at 330', 15 sacks 60' to 0', 15 sacks in rathole. Used 60/40 Pozmix W/ 6% gel. by Howco.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address PO Box 129, Sterling, Kansas 67579

STATE OF Kansas COUNTY OF Rice, ss.

Richard L. Mead (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard L. Mead

(Address) PO Box 129, Sterling, Kansas 67579

RECEIVED
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 16 day of August, 19 90

CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires: _____

F.A. Wuellner
Notary Public F.A. Wuellner



STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

SAMPLE LOG - - - - - F. Massey #4-3
 SW SW NW, Section 3-T24S-R17W, Edwards County, Kansas

OPERATOR: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 10, 1990

COMPLETED: August 16, 1990

LOG

0 - 80'	surface soil & sand
80 - 320'	red bed & shale
320 - 1129'	shale & lime
1129 - 1146'	anhydride
1146 - 4550	lime & shale

CASING RECORD

Ran 7 joints 8 5/8" 23# new casing.
 304.45' pipe set at 317' KB. Cemented
 with 225 sacks 60/40 Pozmix W/ 2% gel
 & 3% cc. Plug down at 12:15 PM 8-10-90
 by Howco. Good returns to surface.

Plugged: August 16, 1990

DEVIATION SURVEY:

4330' 1 1/4°

RECEIVED
 STATE CORPORATION COMMISSION

AUG 20 1990

CONSERVATION DIVISION
 Wichita, Kansas