

KANSAS

Form CP-3  
Rev. 6-4-68  
RECEIVED  
STATE CORPORATION COMMISSION

STATE CORPORATION COMMISSION

OCT 13 1978

CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-095-20644-0000 (of this well)

Operator's Full Name F. M. Pety Corp.  
Complete Address 817-17th St, Denver Colo. 80202  
Lease Name H. M. Fenna Well No. 2  
Location NE NE NE- Sec. 3 Twp. 28<sup>S</sup> Rge. 8 (E) 4 (W) 4  
County Fingerman Total Depth 4006  
Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A         
Other well as hereafter indicated       

Plugging Contractor Falso Casing Pulling  
Address Box 176 - Chase, Kans - 67524 License No. 683  
Operation Completed: Hour 9:45 Am. Day 12 Month 10 Year 1978

The above well was plugged as follows:

254'-8 5/8" Casing of 200 sack Cement - 4 1/2" Casing set @ 400'  
w/ 200 sack Cement - 5' open hole - Sand back to 3975' Top  
sand w/ 4 sack mixed Cement w/ dump bailer & Pull 3125'  
4 1/2" Casing - fluid to cellar - Flowco - mixed & pumped 3 sack  
hulls - 20 sack gel - release plug - mixed & pumped 150 sack  
60/40 pos. w/ 29 gel - 3900 to top of Casing - shut in  
w/ 400# pressure -

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 10-13-78  
INV. NO. 8291-W