

KANSAS
STATE CORPORATION COMMISSION

15-095-302550000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa Bldg., Tulsa, Oklahoma

Lease Name McKenna Well No. # 1

Location C NW SE Sec. 3 Twp. 28 Rge. 8 (E) (W)W

County Kingman Total Depth 4395'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Graybol Oil Corporation

Address: 2200 National Bank of Tulsa Bldg., Tulsa, Ok. License No. _____

Operation Completed: Hour 4:30PM Day 19th Month Sept. Year 1965

The Above well was plugged as follows:

230' of 8 5/8" surface pipe, cement circulated with 185 sacks. Hole
was filled with drilling mud to 200', 1st cementing plug, bridged
solid with dry cement and hulls on fluid at 200', and cemented with
25 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 9/21/65
INV. NO. 1838-14