

15-095-01855-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 9 1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address: Box 308, Great Bend, Kansas

Lease Name Huey Well No. # 1

Location C NW NE Sec. 13 Twp. 28 Rge. 8 (E) (W) W

County Kingman Total Depth 4409'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:00PM Day 7th Month March Year 1966

The Above well was plugged as follows:

413' of 8 5/8" surface pipe, cemented with 275 sacks. 4140' of 2 7/8"
tubing for long string, cemented with 350 sacks. Plug back TD 4097'.
Top perforation 4012'. 10 sacks of cement was pumped on bottom with the
top of the cement at 3800'. 2961' of 2 7/8" tubing was recovered from the
hole. Fluid level in the hole was at 260'. bridge plug and rock bridge from
260' to 250', and cemented with 25 sacks. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/9/66
INV. NO. 2838-W