

2 100293

10-14-87 153

API NUMBER 15-1795-01822-02-02

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NE NE, SEC. 27, T. 28 S, R. 7 W/EX

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153

Lease Name Alameda Unit Well # 5-1

Operator: Texaco, Inc.

County Kingman 145.47

Name & Address

Well Total Depth 4476 feet

Box 2429

Conductor Pipe: Size 5 1/2" feet 4410

Tulsa, OK 74102

Surface Casing: Size 8 5/8" feet 244

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated Perf @4350-55, 3668-74

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: PM Day: 14 Month: 10 Year: 19 87

Plugging proposal received from Don

(company name) Sargent's Casing Pulling (phone) \_\_\_\_\_

were: Perf @4350-55 Squeeze 150 sxs cement to 4270'. Perf 3674-3668 squeeze with 100 sxs cement to 3440'. Shoot pipe and pull. 40 sxs @250'. 10 sxs @40' to surface.

Plugging Proposal Received by Steve VanGieson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:00pm Day: 14 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT Squeeze 150 sxs cement to 4270' on first perf. Squeeze second perf w/100 sxs cement to 3440'. Shot 5 1/2" @2818' and pulled to 244'. Pumped 75 sxs cement to surface

Remarks: Sargent's Well Service Common cement mix on location  
(if additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging)

Signed Johnny Sanders  
(TECHNICIAN)

DATE 2-4-88  
INV. NO. 19733

JAN 28 1988  
01-28-88  
CONSERVATION DIVISION  
Wichita, Kansas