

11-28

2-040585

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-095-01829-0000

C SE NW, SECTION 27 TOWNSHIP 28 RANGE 7W

OPERATOR LICENSE # 5153 3300 FEET FROM S SECTION LINE
660 FEET FROM E SECTION LINE

OPERATOR Texaco, Inc.
NAME & P. O. Box 779
ADDRESS Kingfisher, OK 73750

LEASE NAME: Alameda Ut #6-2
COUNTY: Kingman
WELL TOTAL DEPTH: 4429'

CONDUCTOR PIPE: " @ '
SURFACE CASING: 8-5/8" @ 264'

143.94

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: B. J. Services
ADDRESS: Medicine Lodge, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Gib Arterburn
COMPANY NAME: Texaco, Inc. PHONE: _____

WERE: PBTD @ 3625' - 5-1/2" @ 4424' - perf 4358-4363' - CIBP
3625' - perf 4 hole @ 1100' & circ cmt to surf.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 9:30 DAY: 28 MONTH: 11 YEAR: 1990

ACTUAL PLUGGING REPORT:
Set CIBP 3554' 11/26/90 - Great Guns Perforating shot
4 holes at 1100' - B.J. Services pumped 400 sx 40/60 4%
gel down 5-1/2" csq attempting to circ cmt back up the
annulus - no cmt returns - 11/28/90 Great Guns
perforated 4 holes at 600' and B.J. Services circ cmt
back to surface.

REMARKS: B. J. Service #636322 & #636360 40/60 4% gel 12-05-90

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 12-10-90

INV. NO. 30209

Steve Van Gieson
Steve Van Gieson (AGENT)

RECEIVED
CONSERVATION DIVISION
Wichita, Kansas
DEC 5 1990

FORM CP-2/3
REV. 3/90