

2 050259

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-21, 524 - 6000

CS/2 SENESEC. 24, T 28 S, R 7 W/X

2970 feet from N/S section line

760 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7811

Lease Name Messenger Well # 1

Operator: William's Brothers Engineering Co.

County Kingman 129.45

Name & Address 6600 S. Yale

Well Total Depth 3983 feet

Tulsa, OK 74136

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mustang Drilling License Number 5652

Address Great Bend, KS

Company to plug at: Hour: Day: 21 Month: 6 Year: 19 85

Plugging proposal received from Gib Overbey

(company name) Mustang Drilling

RECEIVED
STATE CORPORATION COMMISSION

were: 35 sacks of cement at 1100 feet

35 sacks of cement at 310 feet

15 sacks of cement at 40 feet

.10 sacks in rat hole

7-9-85
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by W. Kirkpatrick (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: Day: 21 Month: 6 Year: 19 85

ACTUAL PLUGGING REPORT Ran drill pipe to 1100 feet and circulated hole 15 minutes.

Spotted 35 sacks of cement at 1100 feet and displace with mud. Pulled drill pipe to

310 feet and spotted 35 sacks of cement. Pulled drill pipe and pushed plug to

40 feet and circulated cement to surface. Circulated 10 sacks of cement in rat hole.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

(If not) observe this plugging.

DATE 7-19-85

Signed Glenford Ward (TECHNICIAN)

INV. NO. 9034

RO