

2050437

15-09501340-0000

API NUMBER 15- D & C 6-11-62

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NE NE, SEC. 28, T 28 S, R 7 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153

_____ feet from S section line

_____ feet from E section line
Track #7

Lease Name Alameda Unit Well # 2-SWD

Operator: Texaco, Inc.

County Kingman 151.06

Name & Address Box 2420

Well Total Depth 4648 feet

Tulsa, OK 74102

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 222

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor M & B License Number _____

Address _____

Company to plug at: Hour: _____ Day: _____ Month: 9 Year: 19 86

Plugging proposal received from _____

(company name) _____ (phone) _____

were: 5 1/2" casing set at 4561' with 150 sacks of cement - open hole from 4561 to 4648' -
top of cement at 4250' - packer and tubing set at 4102' - tubing pulled into at 1122'
could not get down hole below 580' - fill with cement from 580' to surface

Plugging Proposal Received by SVG (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30a.m. Day: 5 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT Ran 1" tubing to 580 feet and spotted 50 sacks of cement.

Pulled 1" tubing. Waited for cement to set. Pumped down 5 1/2" with 100 sacks of cement.
Closed in at 150# psi. Next day cement had dropped 180 feet. Could not pump into
5 1/2". Ran 1" to 180 feet and circulated cement to surface. Squeezed 8 5/8" surface
pipe with _____ sacks of cement.

Remarks: B.J. Titan #28714

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 9-30-86

Signed Glenn L. Ward (TECHNICIAN)

INV. NO. 15034 OCT 13 1986