

2 070098

To: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT #5403

Operator License # Wayne Walcher

Operator: 710 Bitting Bldg
 Name & Address: Wichita, KS 67202

Abandoned Oil Well _____ Gas Well ☒ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso License Number _____

Address _____

Company to plug at: Hour: 8:30 Day: 9 Month: 8 Year: 19 88

Plugging proposal received from John Sanders

(company name) _____ (phone) _____

were: Pump bottom 30 sx of common - top plug - 3 hulls - 10 gel - 125 sx
 60/40 2% gel

Plugging Proposal Received by _____
 (TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part _____ None _____

Operations Completed: Hour: 9:30 Day: 9 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT Bottom plug was pumped 30 sx of common by Allied - 1700 lbs to

pump plug to 3460' - plug did not hold - some gas leakage so set exsticon bridge
 plug at 3460 and ran 4 sx of common on top of plug.

Allied came back and pumped 3 hulls - 10 gel 125 sx of 60/40 2% gel max press was
 500 lbs shut in was 250 lbs.

Pulled 3340' of 4-1/2"

Remarks: _____

(If additional description is necessary, use BACK of this form.)
 CONSERVATION DIVISION
 Wichita, Kansas

I (and did not) observe this plugging.

DATE 9-8-88

DIV. NO. 22160

API NUMBER 15- 095-20,889 -0001

SW, SEC. 30, T 28 S, R 7 W/X

_____ feet from S section line

_____ feet from E section line

Lease Name Pederson Well # 1

County Kingman 131.63

Well Total Depth 4050 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8-5/8 feet 212

STATE CORPORATION COMMISSION

09-01-88 SEP 1 1988

Signed Jack Luther (TECHNICIAN)