

2 040214

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-095-213850000  
CNE14, SEC. 12, T. 28 S., R. 8 W

3960 feet from N/E section line  
1320 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5471

Lease Name Linguist Well # #1

Operator: Aurora Inc

County Kingman Trust 149.50

Name & Address Bx 12747

Well Total Depth 4600 feet ✓

9505 W. Central #108

Conductor Pipe: Size \_\_\_\_\_ feet

Wichita Ks. 67277

Surface Casing: Size 8 5/8 feet 277

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing License Number 6050

Address Box 176 Chase Ks.

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone) \_\_\_\_\_

were: \_\_\_\_\_

PBTD 4445 Bottom Plug 4000 sand to 3950 w/ 6sk

Perfs 3971-75 2nd Plug 2125 sand to 2075 w/ 6sk

& 3994-21 DV to 2527

5 1/2 3975 3hulls 20 gel 150 #40 6% 3%

Rec 1950 5 1/2 Plugging Proposal Received by Stan Marcotte  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 0800 Day: 27 Month: 9 Year: 19 85

ACTUAL PLUGGING REPORT The well had two sets of open perfs. The bottom set of perforation were covered by push a plug to 4000' and sand was used to fill over perfs. and topped off with 6 sacks of cement. The 2nd set of the perforations were covered by pushing a plug to 2125 and sand above the perfs and topped with 6 sacks of cement. The top was plugged by pumping thru the 8 5/8" 3 sks of hulls, 20 sks of Gel & 150 sks of 40/60 gel 3% CACL

Remarks: HOWCO 351629 MX 375 #1 SI 300 #1 3% CACL

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 10-21-85

OCT 18 1985

Signed [Signature]  
(TECHNICIAN)

INV. NO. 10691

CONSERVATION DIVISION  
Wichita, Kansas

RO

FORM CP-2/3  
Rev. 01-84