

2 100477

3-13

156

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-21,600 - 0000

175' NW C SW SEC. 4, T 28 S, R 10 W/EX

1440 feet from N/S section line

4084 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3711

Lease Name Renner Well # 1-4

Operator: Shepler & Thomas, Inc.

County Kingman 84.50

Name & Address P. O. Box 1162

Well Total Depth 2600 feet

Liberal, KS 67905-1162

Conductor Pipe: Size feet

316-624-0750

Surface Casing: Size 8-5/8 feet 225

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Brandt Drilling Co. License Number 5840

Address Wichita, KS 67202

Company to plug at: Hour: 4:00 Day: 13 Month: 3 Year: 19 89

Plugging proposal received from Tim Brandt

(company name) Brandt Drilling Co. (phone)

were: 35 sx @ 1500' - 35 sx @ 1000' - 35 sx @ 275'

25 sx @ 60' - 10 sx R.H. - 10 sx M.H.

Plugging Proposal Received by Don Thompson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30p Day: 13 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT Spotted 35 sx cement thru drl pipe at 1500' below salt,

pulled pipe to 1000' & spotted 35 sx above salt - at 275' spotted 35 sx - 50' below

surface pulled pipe to 60' & circ 25 sx to surface - put 10 sx in rat hole & 10 sx

in mouse hole.

RECEIVED
STATE CORPORATION COMMISSION
3-24-89
MAR 24 1989

Remarks: Allied 60/40 6% gel CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

I (XXXXX did not) observe this plugging.

DATE 3-30-89

Signed J. L. Sanders (TECHNICIAN)

INV. NO. 24312