

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

12-8-95

2-070586

API NUMBER: 15-159-095-21.231-0000
C-SW-SW SECTION 19 TOWNSHIP 28 RANGE 10W

OPERATOR LICENSE # 3842

660 FEET FROM S SECTION LINE
4260 FEET FROM E SECTION LINE

OPERATOR LARSON ENG
NAME & 562 WEST HIGHWAY #4
ADDRESS OLMITZ, KS 67564-8561

LEASE NAME: ZRUBEK #1
COUNTY: KINGMAN
WELL TOTAL DEPTH: 4600 ^{149.50}

PIPE: _____

SURFACE CASING: 8 5/8" @ 481'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____
PLUGGING CONTRACTOR: DS&W WELL SERVICING
ADDRESS: PO BOX 231, C LAFLIN KS 67525 LICENSE: 6901

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 8 MONTH: 12 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: KEVIN
COMPANY NAME: SAME PHONE: 316-
WERE: SAND TO 2700' AND 4SKS

35 SACKS @ 1600'
35 SACKS @ 1050'
CIRCULATED CEMENT 540' TO 0'

PLUGGING PROPOSAL RECEIVED BY: DL
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL X PART NONE

COMPLETED: HOUR: 3:00 DAY: 8 MONTH: 12 YEAR: 1995
ACTUAL PLUGGING REPORT:

SANDED BOTTOM TO 2700' AND 4 SACKS OF COMMON SHOT 4 1/2" CASING OFF
AT 2087' PULLED TO 1600' PUMPED 35 SACKS PULLED TO 1050' PUMPED 35
SACKS PULLED TO 540' CIRCULATED CEMENTED TO SURFACE

REMARKS: 60/40 4% ALLIED #3735

Jack Luthi (AGENT)

FORM CP-2/3
RECEIVED
KANSAS CORPORATION COMMISSION
REV. 3/90

INVOICED

DATE JAN 30 1996

INV. NO. 44766

JAN 29 1996

1-29-96
CONSERVATION DIVISION
WICHITA, KS