


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

15-095-20187-0000

Kingman County, Sec. 7 Twp. 28S Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines NW-NE
Lease Owner K. W. B. Oil Property Management, Inc.
Lease Name McKenna Well No. 1
Office Address 1125 NBT Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 28 19 69
Application for plugging filed December 1 19 69
Application for plugging approved _____ 19 _____
Plugging commenced November 28 19 69
Plugging completed same 19 _____
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well ~~Ralph J. Watson~~ Herman Justice
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4391 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 240', 1/2 sack hulls, wood plug and 30 sacks cement.
Mud to 40', 1/2 sack hulls, wood plug and 10 sacks cement.
3 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1969
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Aspen Drilling Co.
Address P. O. Box 783, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
William S. Schachle (employee of owner) or (owner or operator) of the above-described

well, being first only sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well filed and that the same are true and correct. So help me God.

(Signature) William S. Schachle
William S. Schachle
Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 1st day of December, 19 69



My commission expires April 18, 1972
Theora Holleman
Theora Holleman, Notary Public.

DRILLERS LOG

COMPANY: K. W. B. Oil Property Management, Inc.
 CONTRACTOR: Aspen Drilling Co.
 LEASE NAME: McKenna #1
 LOCATION: NW-NE Sec. 7-T28S-R8W
 Kingman County, Kansas
 ELEVATION: 1558' K. B.
 SURFACE CASING: 7 jts. (282') 8 5/8"
 COMMENCED: November 18, 1969
 COMPLETED: November 28, 1969
 ROTARY TOTAL DEPTH: 4391'

FORMATION	DEPTH
Shale & Shells	985
Shale & Lime	1485
Lime & Shale	2760
Shale & Lime	2925
Lime & Shale	3072
Shale & Lime	3395
Lime	3788
Shale & Lime	3797
Lime & Shale	3982
Mississippian Lime	4148
Shale	4230
Lime & Shale	4362
Simpson Sand	4391

Ran 7 jts. (282') 8 5/8" casing set
 at 288' w/265 sacks cement.
 Cement circulated.

Ran DST #1, 3988-3999.

D & D

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 8 1969
 CONSERVATION DIVISION
 Wichita, Kansas

AFFIDAVIT

State of Kansas)
) ss:
 County of Barton)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record of the well drilled at the location above described.

William S. Schachle
 William S. Schachle, AFFIANT

Subscribed and sworn to before me this 1st day of December, 1969.

Theora Holleman
 Theora Holleman, Notary Public

