

15-095-01239-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kingman County. Sec. 12 Twp. 28 Rge.      (E) 8 (W)  
Location as "NE/CNW%SW%" or footage from lines G NW NE  
Lease Owner Pickrell Drilling Company  
Lease Name Garlich Well No. 1  
Office Address 705 4th Natl Bank Bldg, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 1 19 63  
Application for plugging filed May 1 19 63  
Application for plugging approved May 1 19 63  
Plugging commenced May 1 19 63  
Plugging completed May 1 19 63  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production      19      
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation      Depth to top      Bottom      Total Depth of Well 4340 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	232	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Heavy mud to 180'. Set plug. Cemented with  
20 sacks cement. Heavy mud to 40'. Set plug.  
Cemented with 10 sacks cement to bottom of  
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 8 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PICKRELL DRILLING COMPANY  
Address 705 4th National Bank Bldg, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

~~KENNETH R. GARDNER~~ (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.

(Signature)


C. W. SEBIS  
705 4th Natl Bank Bldg, Wichita 2, Kansas  
(Address)

Subscribed and sworn to before me this 6th day of May, 1963

My commission expires

June 21, 1966

Maxine Blackman  
Notary Public.



**ROTARY DRILLING LOG**

15-095-01239-0000

COMPANY: PICKRELL DRILLING COMPANY  
 705 4th National Bank  
 Wichita, Kansas

LOCATION: Garlisch No. 1, C NW NE 12-28-8W  
 Kingman County, Kansas

Rotary Drilling Commenced 4-15-63

Rotary Drilling Completed 4-30-63

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
 Wichita, Kansas

CASING RECORD: (6 jts) 8 5/8" Surface Casing set at 232', cemented with 170 sacks cement. Circulated. Completed at 5:30 P.M. April 15, 1963. No oil string run. D & A.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

10	Sand	C. F. S.
232	Red Rock	3632
970	Shale	3640
1335	Shale & Lime	3915
1760	Lime	3938
2890	Lime & Shale	3946
2990	Lime	3953
3245	Lime & Shale	3961
3757	Lime	3980
3935	Lime & Shale	4268
4054	Mississippian	4274
4085	Mississippian Lime	4278
4148	Mississippian	4283
4192	Lime	4288
4252	Kinderhook	4294
4309	Simpson	4310
4310	Viola	4323
4340	Simpson & RTD	4340

**RECEIVED**  
 STATE CORPORATION COMMISSION

MAY 8 1963

CONSERVATION DIVISION  
 WICHITA, KANSAS

Slope Tests

2500  
 3000  
 3500  
 40000

S. L. M.

3302  
 3757  
 4128

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

**PICKRELL DRILLING COMPANY**

By *C. W. Sebitts*  
 C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } ss.:

On this 6th day of May, 19 63, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires June 21, 1966.

*Maxine Blackman*  
 Maxine Blackman Notary Public

