


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-095-20458-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County, Sec. 12 Twp. 28S Rge. 8W (EX) (W)
Location as "NE/CNW/SW" or footage from lines C-SE-SW
Lease Owner Keener Oil Company
Lease Name Mark Tunney Well No. 1
Office Address 406 National Bank of Tulsa Building, Tulsa,
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole OK 74103
Date well completed February 9, 1976
Application for plugging filed verbal application 19
Application for plugging approved verbal approval 19
Plugging commenced February 8, 19 76
Plugging completed February 8, 19 76
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G.R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,020 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD			
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT	
				8 5/8"	249'	none	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,020 feet (rotary total depth) to 240 feet. Set solid plug at 240 feet and cemented with 40 sxs cement. Filled hole with heavy rotary mud from 240 feet to 40 feet. Set solid plug at 40 feet and cemented to cellar with 10 sxs cement. 2 sxs cement in rathole.
Plugging operations accomplished utilizing Halliburton Oil Well Pump Truck through 4 1/2 inch drill pipe.

Name of Plugging Contractor H-30, INC.
Address 200 North Main Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick ss.

Dean Britting - Agent (agent of owner) or (operator) of the above-described well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 North Main Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 16th day of February, 1976



My commission expires June 30, 1978
Elsie Willison Notary Public.


API Number 15-095-20,458 -0000

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Keener Oil Company**
 FARM **Mark Tunney** NO. **1**

SEC. **12 T. 28S R. 8W**
 LOC. **C-SE-SW**

TOTAL DEPTH **4,020'** COUNTY **Kingman**
 COMM. **January 30, 1976** COMP. **February 8, 1976**
 SHOT OR TREATED
 CONTRACTOR **H-30, INC.**
 ISSUED **February 16, 1976**



CASING
 20 10
 15 5/8" 249' cemented w/275 sxs cement ELEVATION **1,544' KB**
 12 6
 13 5

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	10'
Red Bed	270'
Shale	1,330'
Lime and Shale	3,330'
Lime	4,020'
Rotary Total Depth	4,020'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting

 Dean Britting

State of Kansas }
 County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 16th day of February, 1976.



Elsie Willison

 Elsie Willison - Notary Public

My Commission Expires:
June 30, 1978

RECEIVED
 STATE CORPORATION COMMISSION

FEB 18 1976

CONSERVATION DIVISION
 Wichita, Kansas